



Sligo Task Order 10

This Montgomery County project was for the sewer rehabilitation in the Sligo Creek Basin, an environmentally sensitive area.

Completion Date: April 2021

This project, completed in Montgomery County, Maryland, was an Environmentally Sensitive Area (ESA) Sewer Rehabilitation. As a subcontractor on this project, Triangle Contracting executed the pipe installation, sewer external point repairs, and manhole rehabilitation. The manhole rehabilitation work was completed efficiently with Triangle Contracting's pipe bursting method.

The pipe bursting method was used to upsize from an existing 6" pipe to an 8" pipe. The new 8" sewer main was connected to the existing manhole and matched to the existing invert. Triangle Contracting effectively and efficiently executed these pipe installations, manhole rehabilitations, and sewer point repairs.

